75	10.00	Supplyin mmdia 2mm 2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive pase etc., and running before cocreting the slab. The conduit should be tiled to the reinforcement rods by using binding wires and unused ways of junction boxes and plpe ends should be covered using PVC end enclosuers. Run with 18SWGGI fish wire wherever necessary	Nos	48.00	Rupees Forty Eight Only
76	1.00	Supplying of TPST with rewirable porcelain channels in SM enclosure. (P-30. 1-1)	Rmtr	1612.00	Rupees One Thousand Six Hundred Twelve Only
77	2.00	Supplying and fixing polished wood board made of not less than 15 mm thick plan on both sides with planks made out of more than two pieces and fixing the same to the wall using wooden plugs, screws etc.,	Nos	338.00	Rupees Three Hundred Thirty Eight Only
78	1.00	Supplying and wiring adopting loop system in existing PVC Conduit/casing caping using Copper PVC insulated multistrand 2x1.5 Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box. The other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet .....(a) Short Point upto 3Mtr form tapping point to outet via switch	Rmtr	207.00	Rupees Two Hundred Seven Only
79	1.00	(b)&#65533; Long Point above 6 Mtr. Upto 10 Mtr. From tapping point to out let via switch	Rmtr	436.00	Rupees Four Hundred Thirty Six Only
80	1.00	Supplying 6 A flush/projected type socket and a 6Amps flush/projected type SP switch either surface/flush mounting in a existing gang box or a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required (b)6Amps3/5 Way	Nos	125.00	Rupees One Hundred Twenty Five Only
81	25.00	Wiring for lighting /power circuit using one of PVC insulated 1100V grade multis and Copper conductor single core cable in open or consealed system of wiring (P-9, 1-20)Group "B"&#65533; 2.5Sq.mm	Rmtr	24.00	Rupees Twenty Four Only
82	3.00	Supplying and fixing PBBC backelite straight or slant batten holder &wiring 60w/230 Volts lamps	Rmtr	66.00	Rupees Sixty Six Only
83	3.00	Supplying and fixing of LED type panel borad indicating lamp with required colour suitable for 220 v A.C. 50 Hz 12/24v D.C	Nos	510.00	Rupees Five Hundred Ten Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contratror

Scanned by CamScanner

84	12.00	Supplying of LT UG cable having aluminium conductor PVC insulated. Sheathed. Galvanished. Steel wire/steel tape armoured cable with PVC outer sheathing 1.1KV class (conforming to IS 1554) Class-A (P-67, 1-10).....e)4.0 core 16Sqmm	Rmtr	178.00	Rupees One Hundred Seventy Eight Only
85	12.00	Lobour charges for laying of 1.1KV class UG cable when supplied departmentally/ agency in existing trench GI pipe/stoneware pipe/on wall/on pole as required a)10Sqmm to 16Sqmm	Rmtr	9.00	Rupees Nine Only
86	8.00	Digging of trench of 0.6mtrs deepx0.5 mtrs wide refilling the required gorund level and consolidating etc., complete a)in soil(ordinary)	Rmtr	47.00	Rupees Forty Seven Only
87	6.00	Supplying and fixing of class 'A' GI pipe on pole /wall/drain crossing with necessary clamping arrangement for UG cable of 1.1KV class)a)65mm(upto 150Sqmm)	Rmtr	284.00	Rupees Two Hundred Eighty Four Only
88	1.00	Supplying and fixing of heay duty cable glands suitable for UG cable of 1.1KV class metal only a)25mm dia	Nos	78.00	Rupees Seventy Eight Only
89	1.00	Supplying and fixing miniature circuit breakers on existing MCB disitribution boards using necessary fixing materials and wiring complete as required 5-32 amps TPN	Nos	1191.00	Rupees One Thousand One Hundred Ninety One Only
90	5.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers etc., complete a) 32Amps	Nos	118.00	Rupees One Hundred Eighteen Only
91	1.00	Supplying and fixing L.T. cast Iorn pot heads suitable for 1.1. KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., a) 16Sqmm	Nos	308.00	Rupees Three Hundred Eight Only
92	1.00	Supplying, fixing, wiring, earth electrode for gounding conduits, I.C cotouts and other equipments on the meter board using 40mm dia 2.90 thick GI pipe 2.5 mtr long buried in a pit... The pit should be filled with equal proprotion of salt and charcoal 150mm alround the pipe to complete depth. The connection from the to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and checkunts etc., the pipe shall have 16 through holes of 122mm dia	Nos	2312.00	Rupees Two Thousand Three Hundred Twelve Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

93	1.00	Supplying decorative horizontal type street light fluorescent fitting weather and water proof complete with low loss open construction copper wound ferromagnetic ballast,starter,locking type brass contact holders with 1 No. of 4 feet 40 watts fluorescent tube completely wired for use on 230/250 volts. 50cycles AC supply with opal reeded Perspex cover at bottom complete fitting	Nos	1695.00	Rupees One Thousand Six Hundred Ninety Five Only
94	1.00	Supplying & fixing mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluroscent tube street light fitting of all capacities of GI or CI or rail or RCC pole/ wall using suitable clamps. bolts. and nuts and wiring using suitable capacity wires complete(	Nos	723.00	Rupees Seven Hundred Twenty Three Only
95	25.00	Supplying heavy gauge PVC conduit pipe…… dia confirming to IS 2509 with suitable size benda, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall stone structure or rawl plugs in case of brick walls and cement plastering damaged portion using heavy gauge saddles at an interval of 700mm using NF screws. b) 25mm dia 2mm thick	Rmtr	49.00	Rupees Forty Nine Only
96	25.00	Supplying…… mm dia 2mm/2.5mm thick heavy gauge PVC conduit pipe with suitable size bends, metal/PVC junction boxes adhesive paste etc., and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures. run with 18SWG GI fish wire wherever necessary. b) 25mm dia 2mm thick	Rmtr	45.00	Rupees Forty Five Only
97	20.00	Groove cutting in the wall supplying…..dia 2mm/2.5mm thick heavy gauge PVC Conduit Pipe with bends, metal junction boxes adhesive paste etc., and bracing U or J hooks and cement plastering up to the surface of the brick level and run with 18 SWG GI fish wire run through out conduit wherever necessary. b) 25mm dia 2mm thick	Rmtr	58.00	Rupees Fifty Eight Only
98	1.00	Supplying and fixing sheet metal box made out of 18 SWG sheet metal with necessary holes for cable/conduit entry as required with one coat of approved make etc……c) 135x75x65mm	Each	94.00	Rupees Ninety Four Only
99	1.00	d)180x90x65mm	Each	129.00	Rupees One Hundred Twenty Nine Only

Executive Engineer
RRNagara Division
BBMP

Signature of the contractor

Scanned by CamScanner

100	1.00	e)200x90x65mm	Each	140.00	Rupees One Hundred Forty Only
101	1.00	Supplying and fixing PVC/metal conduit accessories.(3/5) (ELE SR 2010-11 Page-3, Item-5).....1. Special type junction box.....b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box	Each	44.00	Rupees Forty Four Only
102	5.00	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work cpmplete.....a)12xx"12"x3" (330x300x76mm	Rmtr	107.00	Rupees One Hundred Seven Only
103	5.00	b)12"x9"x3" (300x228x76)	Rmtr	88.00	Rupees Eighty Eight Only
104	2.00	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. compelete for each outlet.....a) Short point up to 3Mtr from tapping point to out let via switch	Each point	192.00	Rupees One Hundred Ninety Two Only
105	2.00	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch	Each point	285.00	Rupees Two Hundred Eighty Five Only
106	2.00	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet.....a) Short point up to 3Mtr from tapping point to out let via switch box	Each point	148.00	Rupees One Hundred Forty Eight Only
107	2.00	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box	Each point	247.00	Rupees Two Hundred Forty Seven Only
108	5.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. .....e) 6Moudule	Each	137.00	Rupees One Hundred Thirty Seven Only

Signature of the contratror

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

109	2.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate. a) 6Amps one way.	Each	105.00	Rupees One Hundred Five Only
110	2.00	i) 32Amps DP switch	Each	401.00	Rupees Four Hundred One Only
111	2.00	j) 6/16Amps universal socket	Each	225.00	Rupees Two Hundred Twenty Five Only
112	2.00	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply &completely wired on existing box. ……Group 'A'	Each	691.00	Rupees Six Hundred Ninety One Only
113	60.00	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multistrand Copper conductor single core cable in open or concealed system of wiring. ……..a. 1 sqmm.	Rmtr	12.00	Rupees Twelve Only
114	60.00	b. 1.5 sqmm	Rmtr	16.00	Rupees Sixteen Only
115	53.00	C.6 sqmm	Rmtr	57.00	Rupees Fifty Seven Only
116	10.00	Supplying and fixing of PVC casing and capping on the wall or ceilng using necessary materials like bends, screws at an interval of 300mm …. Etc as required……..a) 20mm	Rmtr	39.00	Rupees Thirty Nine Only
117	12.00	Supplying PVC/GI flexible conduit pipe….mm dia fixing on surface over inverted wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pipe terminated completely…….a) 20mm	Nos	49.00	Rupees Forty Nine Only
118	12.00	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws……b) 110mm	Nos	9.00	Rupees Nine Only
119	20.00	Supplying a 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slab.	Nos	4.00	Rupees Four Only

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

120	26.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement &the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.) 20mm nominal OD pipes	Rmtr	233.00	Rupees Two Hundred Thirty Three Only

Signature of the contratror

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner